

St Oswald's Church, Malvern Way, Croxley Green WD3 3QL (cost added)

Specification for Alterations to Church Kitchen (see Dwgs 2201/1 & 2)

Alterations to kitchen units: elevation A - £8,903 incl. vat

Remove existing sink and worktop. Supply and fit new worktop in 38mm bullnose laminate in oak effect to match existing where existing sink removed. Adjust cupboard and drawer fronts as shown.

Supply and set in new stainless steel single drainer sink unit and new circular stainless steel hand wash sink into new work top.

New waste pipe to the drain, and mixer tap to new sink with lever handles.

New waste pipe to the drain and lever cold tap to handwash sink. Existing hot water unit is to provide hot water for hand washing.

Provide cold water supply to new sink, and new under counter electric 15L 2 kw water heater for washing up at the sink, via the mixer tap, complete with all necessary pressure vessels and relief valves. Provide new electrical supply via appropriate 13 amp fused switched spur from existing ring main circuit.

Provide and install new plumbed in wall mounted over counter water boiler of 25L capacity (Heatrae Sadia 310SS 2.8kW [£1,979 incl. vat from Boilers Direct] or equal approved), complete with all necessary pressure vessels and relief valves. Provide new electrical supply via appropriate 13 amp fused switched spur from existing ring main circuit.

Provide 300 high white gloss ceramic tile splashback full length of the wall and returning 600 on each end wall.

New wall cupboards: elevation B

Supply and install wall cupboards in Howdens Greenwich super matt handle less range as shown in white colour. 900h 300d 2No 500w 1 No 600w.

Remove one base unit and provide power point and supply and install under counter fridge with ice box.

Lights – install new plastic diffusers to existing strip lights.

Mobile Servery unit and back wall worktop in Church area - £3,360 incl. vat

(separate quote for this please)

3 No units 900/850*h 600w 600d on each side. Supply and install units from the Howdens Greenwich super matt handle less range as shown in oak colour.

38mm bullnose laminate work tops in oak colour.

Mobile servery unit to have square edge and oversize top with front overhang (and end overhang of 150) and rounded corners to top as shown on the drawing to the front servery counter.

Work top to mobile servery counter to be 850 wide so the unit can be wheeled through the door (1000 wide) into the kitchen. *Units against the wall to be 900 high (to work top), and the island servery unit to be 850 high (Reduced plinth) so that it is accessible.

All base units to be fitted with two deep drawers. Each run of units to have an oak effect décor panel on the end, and the servery unit to have a breakfast bar back panel décor panel in oak effect. Supply and fix recessed black plinth on three sides of the servery unit, and on the front of the backwall worktop run of units.

Island unit to be mounted on heavy duty castors so it can be relocated if necessary. Castors to be mounted behind plinth with 25 gap under plinth. Plinth secured to the units above. Two castors at the back to have brakes accessible through a gap in the plinth.

Low level Belfast sink for use by flower arrangers - £779 incl. vat

Certification by electrician (estimate) - £450

Total quote from RH Builders (addition of above) - £13,500 incl. vat (rounded)

Quote dated 2/11/23

GP 03/11/23